BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT45020

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2020-21, Date: 19-09-2020

Name of Work:Package-1, includes 5 works of Rs.300.00 lakhs

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Chidananda Murthy R	
				In Figures	In Words
1	1577.88	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	256.07	Rupees Two Hundred Fifty Six and Seven Paise Only
2	10519.2	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	116.87	Rupees One Hundred Sixteen and Eighty Six Paise Only
3	2629.8	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	779.10	Rupees Seven Hundred Seventy Nine and Ten Paise Only
4	701.28	Providing and laying Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days etc complete as per specifications and directions of engineer in charge of the work	cum	5693.00	Rupees Five Thousand Six Hundred Ninety Two and Ninety Nine Paise Only
5	6233.6	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	1028.41	Rupees One Thousand Twenty Eight and Forty One Paise Only
6	749.65	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	cum	5879.98	Rupees Five Thousand Eight Hundred Seventy Nine and Ninety Seven Paise Only
7	6829.2	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	1015.06	Rupees One Thousand Fifteen and Five Paise Only
8	37940	Providing chamfering edges to stone slab 2.5 cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	64.49	Rupees Sixty Four and Forty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

7/12

7/12